

RIG ABAN II

Rig Type	Jack up
Design & Class	Bethlehem Steel Corporation, JU-250MS; Mat Support; MODU ABS +A1
Construction & Conversion Year	Bethlehem Steel Corporation, Sparrows Point, Md, 1981
Flag	Panama
Water Depth	250'
Drilling Depth	25,000'
Quarters	90 Persons
Hull	166' X 132' X 16'
Variable Load	Afloat Condition -2,555 Kips Jacking Condition-2,334 Kips Drilling Condition-4,500 Kips Storm Condition-3,500 Kips
Heliport	60' X 70'
Storage	Mud & Cmt Bulk-6,600 cft; Liquid Mud-1,500 bbls; Fuel-1,750 bbls; Drill Water-4,700 bbls; Pot Water-450 bbls
Drilling Equipment	Draw works-MIDCO 1220; Driven by 2 EMD M79 DC Motors. Mud Pumps-2 Gardner Denver PZ11, Triplex, 1,600 HP, Driven by 2 EMD M79 DC Motors each. Prime movers-Three 12 CYL EMD, 1,650 HP each; DC-DC System; Rotary Table-Gardner Denver ;37 1/2"; Independent motor driven Top Drive-Varco TDS-11 SA
Derrick	Branham 147' X 30' X 30'; 1,392,000 lbs.
BOP System	One Double 13-5/8" x 10M Cameron - Type U Ram Preventer One Single 13-5/8" x 10M Cameron - Type U Ram Preventer One 13-5/8" x 5M SHAFFER Annular Preventer One 21-1/4" x 2M Hydril MSP Annular Preventer 20" Regan Diverter
Cranes	Two Sea King 1400; 19.66 Tons
Mooring	Nil
Positioning	Nil
Work Area	East coast, India
Former Names	Griffin Alexander-III
Nett Registered Tonnage	1556
IMO Number	8750015

